THE WHALEN W COMPANY

EASTON, MARYLAND

MODEL NO.	Serial No.	Refrigeration Chassis No.
VI - A - 602 - BO	**604 XXXXX**	**WA6 - BOT2**

Compressor RLA	Compressor LRA	Fan Motor FLA	Refrigerant 22 Factory Charged.
7.9	**48.3**	**1.1**	**28.5 OZ**

Test Pressure	Voltage	Hertz	Phase
300 PSI	**208 - 230**	**60**	**1**

MILAND
HVAC SUPPLY CO.

Minimum Circuit Ampacity 11.0

MaximumFuse Size **15**

or HACR type circuit breaker

Minimum Voltage 197

2699

Cooling A27 - W30 5 kW

Heating A20 - W20 7 kW